

Corrigendum to NIQ No.-06/17-18 dated 14/09/2017

i. After column 11 of Technical Quotation at page no. 12 of Annexure III following addition be made as column 12

Sl. No.	Description	Unit	Quantity	Make/ Model
12	Supply, Erection, testing and commissioning of Six Pole Structure with following items:			
(A)	06 metre dia 150mmG.I. Pipe	Nos	6	
(B)	Channel 150x100 mm (18 feet)	Nos	2	
(C)	Channel 150x100 mm (10 feet)	Nos	12	
(D)	Channel Clamp with Nut Bolt	Nos	30	
(E)	33 kV Jointing kit Outdoor 185 sq.mm	Nos	5	
(F)	33 kV Jointing kit Indoor 185 sq.mm	Nos	3	
(G)	Pipe earthing with all materials	Nos	2	
(H)	33 KV Isolator (800Amp) with gear box complete set	Nos	2	
(I)	Panther Conductor 200 sq. mm	Meter	30	
(J)	PG Clamp Double Nut Bolt	Nos	18	
(K)	Nut bolt	Nos	As per site requirement	
(L)	33 KV Service Cable 185 sq.mm	Meter	150	

ii. After column 11 of Financial Quotation at page no. 16 of Annexure IV following addition be made as column 12

Sl. No.	Description	Unit	Quantity	Make/ Model	Unit Price (Rs.)	Tax (Rs.)	Total (Rs.)	Remark
(A)	06 metre dia 150mmG.I. Pipe	Nos	6					
(B)	Channel 150x100 mm (18 feet)	Nos	2					
(C)	Channel 150x100 mm (10 feet)	Nos	12					
(D)	Channel Clamp with Nut Bolt	Nos	30					
(E)	33 kV Jointing kit Outdoor 185 sq.mm	Nos	5					
(F)	33 kV Jointing kit Indoor 185 sq.mm	Nos	3					
(G)	Pipe earthing with all materials	Nos	2					
(H)	33 KV Isolator (800Amp) with gear box complete set	Nos	2					
(I)	Panther Conductor 200 sq. mm	Meter	30					
(J)	PG Clamp Double Nut Bolt	Nos	18					
(K)	Nut bolt	Nos	As per site requirement					
(L)	33 KV Service Cable 185 sq.mm	Meter	150					

iii. Amended columns of Annexure IV be read as follows:

Sl. No.	Description	Unit	Quantity	Make/ Model	Unit Price (Rs.)	Tax (Rs.)	Total (Rs.)	Remark
---------	-------------	------	----------	-------------	------------------	-----------	-------------	--------

2. All other terms and conditions of the NIQ 06/17-18 will remain unchanged.

Prof. S. P. Singh
Registrar